




# **SURE-FEED BROADCASTER**

Instructions for Assembly, Mounting, Broadcasting, Operating and Maintenance Repair Parts List







# PARTS AND ACCESSORIES FOR MODEL GT-77-ATV BROADCASTER

When Ordering Parts, Please Order by Both Part Number and Description, Not Drawing Number.

Drawing			Number Needed	
Number	Part Number	Description		
1	500	Grey-Iron Base for GT-77	1	
3 & 4	410A	1/2" x 1" hexhead capscrew with lock washer	2	
3	911	Hopper complete with screws & decals	1	
9 & 11	912	Lid with cotter key	1	
10, 12, 13	913	Lid spring with screw, washer, & nut	1	
14	778	12-volt Motor with Whiz Nuts (#779)	1	
15	501	Fan, 4-bladed (plastic), 5/16" shaft hole, with Setscrews	1	
16	502	1/4" x 3/8" socket screw (included with 501 fan)	2	
17	779	Whiz Nut (10-32), used on motor	2	
19	812	Complete wiring assembly	1	
23	794	Push-Pull switch	1	
26	541	Switch Bracket	1	
30	107	1/4" x 1/2" hex head capscrew	1	
31	512	Brace Rod (Used on Carton "D" only)	4	
32, 33, 34	407	5/16" x 1" Machine Bolt with Nut and Lockwasher	2	
35, 36, 37	924	Brace Rod Clamp Complete (Used on Carton "D" only)	2	
12	781	Round Head Machine Screw, LH Thread	1	
43	507	3/16" x 3/8" Roundhead Machine Screw with Washer	1	
44, 45	503	Bronze Agitator Bushing - Used on Fan & Pivot Plate	2	
46	209	Vibrating Agitator, stainless steel	1	
47	508L	Nipple, used on agitator	1	
48	*517M	Blocking Plate - Optional	1	
49	8025	Pivot Plate, Stainless Steel	1	
50	510	3/16" x 3/8" Roundhead Machine Screw with Washer	4	
51	509	Guide Assemblies for Seed Gate (Set of 2) - Stainless	2	
52	504	Opening Plate with Connecting Linkage - Stainless	1	
53	803S	Opening Gauge Control Plate with #515 Carriage Bolt, Wing Nut, and Washer; Works with Pivot Plate #802S	1	
54, 56, 57	515	1/4" x 1/2" carriage Bolt, Stainless, with wing nut & washer	1	
58, 59	516	1/4" x 1/2" hexhead capscrew, stainless, with washer	2	
60, 61	505	1/4" x 1/2" pan head bolt, stainless, with locking nut	1	
62	792	Control Handle		
63, 64, 65	806A	3/16" x 1-3/4" Machine Screw, with nut & washer		
56	807	Compression Spring - used on handle bolt	1	
67	831	"HERD Sure-Feed Broadcaster" Decal		
58	210	"Model GT-77" Decal		
69	1091	"WARNING - Spinning Blades" Decal	1	
70	408A	#10 x 3/4" Phillips Truss Head Machine Screw with Nut	4	





CHART FOR HERD	BROADCASTE	R GT-77			
LECTRIC MOTOR	POWERED FUL	L SPEED	ON 12 VOL	TS	
				-	<del>                                     </del>
		Amount	Opening	Speed	Time Require
Material	Spread Width	Per Acre	Width	MPH	Per Acre
llover, Alfalfa, & Sweet					
Clover	28'	10#	1/8"	4	4 Min. 25 Sec.
Citates	28'	6.6#	1/8"	6	2 Min. 57 Sec.
	28'	5#	1/8"	8	2 Min. 13 Sec.
Sermuda Grass (hulled)	20	UTT .	1/0		2 Mill. 13 Sec.
Set Base on H	22'	9#	1/8"	6	3 Min. 45 Sec.
Set base on n	22'	6-3/4#	1/8"	8	
	_				2 Min. 49 Sec
V - 1 - 10 - 10 - 10 - 10 - 10 - 10 - 10	22'	5.4#	1/8"	10	2 Min. 15 Sec.
Kentucky Blue Grass	8'	23#	5/16"	4	15 Min. 28 Sec
	8'	15-1/2#	5/16"	6	10 Min. 19 Sec
	8'	11-1/2#	5/16"	8	7 Min. 44 Sec.
Rye Grass & Red					
Fescue	14'	22#	7/8"	4	8 Min. 50 Sec.
	14'	14-3/4#	7/8"	6	5 Min. 54 Sec.
	14'	11#	7/8"	8	4 Min. 25 Sec.
Red Top	10'	17#	1/4"	4	12 Min. 23 Sec
	10'	11#	1/4"	6	8 Min. 15 Sec.
	10'	8-1/2#	1/4"	8	6 Min. 11 Sec.
Highland Bent	10'	18-1/2#	3/8"	4	12 Min. 23 Sec
riigiilaria berk	10'	12#	3/8"	Ġ	8 Min. 15 Sec.
	10'	9.2#	3/8"	8	6 Min. 11 Sec.
Switch Grass	24'	5#	1/16"	10	2 Min. 4 Sec.
Fertilizer	24'	62#	5/8"	4	5 Min. 9 Sec.
retuizer			5/8"	6	
	24' 24'	41#		_	3 Min. 26 Sec.
D II	24	31#	5/8"	8	2 Min. 35 Sec.
Nitrogen (Pelleted 45%				_	l
Urea)	18'	82#	5/8"	4	6 Min. 53 Sec
	18'	55#	5/8"	6	4 Min. 35 Sec.
	18'	41#	5/8"	8	2 Min. 35 Sec.
HART FOR BROAD	DCASTING SEE	DS AND F	ERTILIZER	1	
IGURED AT 4 M.P.					
IOUNED AT 4 M.I .	<u></u>				
		AMT.			
SEED OR	SEED	PER			
MATERIAL	OPENING	ACRE	WIDTH		
MATERIAL	OI LINING	AVINE	WIDTH		
Ammonium Nitrate	3/8"	8 lbs.	24 Ft.		
Australlian Pea	3/8"	60 lbs.	34 Ft.		
Bahia Grass	3/16"	19 lbs.	18 Ft.		
Brome Grass	1/2"	11-1/2 lbs.	14 Ft.		
Flax & Millet	1/4"	8-1/2 lbs.	30 Ft.		
Ladino Clover	1/32*	1 lb.	28 Ft.		
Lespedeza	3/16"	6 lbs.	28 Ft.		
Oats	1"	64 lbs.	26 Ft.		
Orchard Grass	3/8"	9 lbs.	18 Ft.		
Rye	1/2"	42 lbs.	32 Ft.		
Sweet Sudan Grass	1/2"	20 lbs.	28 Ft.		<del>                                     </del>
Timothy	3/16"	6 lbs.	26 Ft.		
Turnin Cood	1/4"	10 lbc	28 5		
Turnip Seed Vetch	1/4" 3/8"	10 lbs. 40 lbs.	26 Ft. 36 Ft.		

### ASSEMBLY INSTRUCTIONS FOR ALL A.T.V.'S.:

- 1. Take broadcast seeder GT-77 from carton and place it upside down on the hopper.
- 2. Rotate handle around and remove bolt and self-locking nut. Run bolt through seed-gate linkage, then

through the handle, making sure that the thread end is pointing up, toward you.

Replace self-locking nut. Do not over-tighten, as it must pivot at this point.

- 3. Remove the two 1/2" bolts from the grey-iron base part number 500 and keep these for mounting of ATV mounting brackets.
- 4. Follow the supplemental instructions for mounting the GT-77 seeder to your specific A.T.V.

# WIRING INSTRUCTIONS

- 1. Be safe! Disconnect ground wire from battery before wiring.
- 2. Connect the short line with the fuse (20 Amp) in the line to the battery on the positive (+) side.
- 3. Be sure to replace safety cap over battery terminal, if one is furnished.
- 4. Connect forked end of long wire to either terminal on switch. Connect female end to male end of "Quick- Connector" on fuse line.
- 5. Connect orange wire from motor to other terminal on switch.
- 6. The black wire on the motor is the ground. Make sure it is connected to the bottom of the motor. It is best to run a ground wire from the battery to any part of the frame or seeder. If that does not work, splice into the ground (black wire) on the motor to the battery ground.
- 7. Reconnect vehicle ground to battery.
- 8. Same as #5.

#### CLEANING AND STORAGE OF BROADCASTER

After removing the broadcaster from the A.T.V., turn it upside-down on the hopper, so that all material

remaining in the hopper is removed. Then wipe or brush out any remaining material. If compressed air is

available, use it to blow off any residue from the broadcaster and the electric motor.

The electric motor is sealed and does not require any maintenance, other than removing any external residue. If the broadcaster is used to spread corrosive material like fertilizer or ice melter, wiping a fine film of oil on the working parts will keep them working free in the future. The pivot plate and all the parts attached to it are made of stainless steel and are rust-resistant for years of life. The fused end of the "Quick-Connect" battery lead may be left on the A.T.V. for future use but be sure to disconnect the wiring harness at the disconnect socket and not at the fuse holder. The broadcaster should be stored in a dry storage area when not in use. High moisture areas will cause condensation internally to the motor and will significantly shorten the motor life.





### TIPS FOR USING BROADCASTERS

- 1. WATCH YOUR SPEED! Do Not Go Too Fast For Conditions. If Ground Is Rough, Cut Your Speed. Remember when seeder is loaded it causes much strain on A.T.V.s and hitch brackets when you start bouncing through holes and rough ground. The hitches were designed for normal usage, so do not get carried away and go too fast.
- 2. As is common with all broadcast seeders, do not use on windy days as this will cause erratic spread, especially with herbicides and may cause damage to crops in nearby fields.
- 3. If your equipment (or vehicle) has a battery and charging system, keep your R.P.M.s sufficiently high enough to charge at all times.
- 4. The easy way to determine the ground speed of your A.T.V. or tractor is to set two stakes in the ground, 88 feet apart, and check with the chart below.
- At 2 M.P.H. you will travel 88 ft. in 30 seconds
- At 3 M.P.H. you will travel 88 ft. in 20 seconds
- At 4 M.P.H. you will travel 88 ft. in 15 seconds
- At 6 M.P.H. you will travel 88 ft. in 10 seconds
- At 8 M.P.H. you will travel 88 ft. in 7 1/2 seconds
- 5. After determining the gear and throttle settings of the A.T.V. mark the settings so the throttle can be returned to the proper location when broadcasting.
- 6. This broadcaster is equipped with a centering pivot plate, which can be moved to center the spread of material. To change location, loosen two capscrews holding pivot plate to bottom of base and move it to a higher or lower letter by taking hold of the seed gauge and moving as explained in next step. A good starting point is to move the seed gauge to the letter "C" for most Clover, Alfalfa and Fertilizers.
- 7. If you see your spread is heavy on one side or the other, after you start to spread, do the following to center the pattern of spread: (You distinguish the difference between right and left by standing behind the A.T.V. or tractor and broadcaster and facing the direction the A.T.V. or tractor will travel.)
- (a) When the pattern of spread is off-center to your right, move the pivot plate to a lower letter.
- (b) If your spread is off-center to your left, move the pivot plate to a higher letter.
- (c) Do not move over one letter at a time or you may over-correct.

# **INSTRUCTIONS FOR INSTALLING OPTIONAL BLOCKING PLATE 517**

- 1. Loosen two capscrews holding pivot plate to base and center pivot plate.
- 2. Remove pivot screw and bushing in pivot plate that anchors agitator to pivot plate. Slide the blocking plate under agitator and over the four protruding screws, making sure that protrusion lays down in opening of pivot plate and blocking plate is flat against pivot plate.
- 3. Replace pivot screw and bushing. Tighten but do not over-tighten. If it is over-tightened, end of screw will extend through pivot plate in bottom and block movement of opening plate.

### TO REPLACE VIBRATOR BUSHING ON FAN

- 1. Remove nipple from pivot plate hole.
- 2. Remove round head machine screw and bushing holding agitator to pivot plate.
- 3. Move agitator forward and at the same time, turn fan so that agitator can be removed from bushing on top of fan.
- 4. Remove agitator from opening.
- 5. Turn fan so that bushing and round-head screw can be removed through opening
- 6. Remove bushing from fan by the following: This round-head machine screw is left-hand threaded, so turn right to loosen.
- 7. Replace new bushing. Tighten the left-hand screw tight.
- 8. Replace agitator through opening, positioning agitator on fan by turning fan so the bushing is placed between forks on agitator.
- 9. Replace bushing and round-head machine screw that holds agitator to pivot plate.
- 10. Replace nipple in round opening.

### TO REPLACE NIPPLE

- 1. Remove nipple from pivot plate hole.
- 2. Remove round-head machine screw and bushing holding agitator to pivot plate.
- 3. Move agitator forward and at the same time, turn fan so that agitator can be removed from bushing on top of fan.
- 4. Remove agitator from opening.
- 5. Remove nipple from agitator.
- 6. Install new nipple on agitator. (A little moisture on nipple where agitator goes through will ease the operation.)
- 7. Replace agitator through opening, positioning agitator on fan by turning fan so the bushing is placed between forks on agitator.
- 8. Replace bushing and round-head machine screw that holds agitator to pivot plate.
- 9. Replace nipple in pivot hole.

# TROUBLE SHOOTING

If motor will not run, turn switch to "Off" position and turn motor by hand to be sure that it turns freely.

Check **ground**, check fuse (this is a 20-amp fuse), check battery connections and battery, and then turn switch to "On" position. The unit should run if the motor is not damaged. For erratic spread of fertilizer or insecticides, check for lumps in material.

# LIMITED WARRANTY

This Herd Broadcaster was thoroughly tested before it left the factory. We warrant each Broadcaster sold by us to be free from defects in material and workmanship when used according to our directions. Our obligation under this warranty is limited to making good at the factory any defective part or parts thereof which shall, within three (3) months after delivery of such Herd Broadcaster to the original purchaser, to be returned to us. No person or company is authorized to make further warranty. This warranty shall not apply to any Herd Broadcaster which shall have been repaired or altered outside of our factory in any way so as to affect its stability or reliability, nor which has been subject to misuse, negligence or accidents, or was caused by damage while in possession of the consumer or resulted from failure to the consumer to provide reasonable and necessary maintenance.



